



Remove existing concrete pin kerb and replace with 75mm wide granite (GR 917) pin kerb.

Existing section of kerb to be retained

Union Canal

- Kerb Layout Legend**
- Extent of works
  - Union Canal
  - Existing Towpath Edge
  - Existing Retained Granite Pin Kerb  
75mmx600mm long, flush
  - Existing Retained Granite Kerb
  - Existing Concrete Pin Kerb to be replaced with 75mmx600mm long, flush, granite (GRA917) pin kerb, by Marshalls or similar approved
  - Proposed Delineation Pin Kerb (flush)  
Granite (GRA917) by Marshalls or similar approved  
75mm wide x 150mm x 600mm long, flush pin kerb to match existing  
Refer to drawing 1504.L.D(94)002 for detail
  - Proposed Wide Kerb (flush)  
Granite (GRA921) by Marshalls or similar approved  
300mm wide x 125mm x 450mm long, flush kerb  
Refer to drawing 1504.L.D(94)002 for detail
  - Proposed Towpath Edging Kerb (flush)  
Granite (GRA921) by Marshalls or similar approved  
150mm wide x 125mm x 450mm long, flush kerb  
Refer to drawing 1504.L.D(94)002 for detail

**Notes**

Work to written dimensions only  
All dimensions to be checked on site  
Do not scale from drawing  
Any drawing errors or inconsistencies should be brought to the attention of rankinfraser landscape architecture as soon as they become apparent.

REV	date	revision notes
-	05.01.16	For Information

Issue	date	Issue notes
-------	------	-------------

**rankinfraser**  
landscape architecture

**project** project nr 1504  
Fountainbridge\_Gibson Terrace to Viewforth Bridge

**drawing title**  
Edging Layout Plan

**client**  
Scottish Canals

**drawing nr** rev  
1504.L.G(92)002 -

**date** **scale**  
05.01.2016 1:250 @ A0

**Issue**  
information  
biling  
tender  
construction  
as built

6 Darnley Street, Edinburgh EH3 6BQ  
0131 226 7071  
mail@rankinfraser.com www.rankinfraser.com