



Tusk of standing wall core from South.
Small holes and pockets to be checked, pinnings/core stones to be checked for fixity.
Wall capping consolidation mortar to be checked and renewed if cracked and unstable.
All sound original mortar to be retained. All sound earlier conservation mortar to be retained.
Only cracked and failing mortar leading to unstable stones is to be renewed.

Estimated new mortar to be placed to be less than a total 2 sq. m. Works being undertaken to ensure fixity for H&S masonry stability.



Tusk of standing wall core form North.

Small holes and pockets to be checked, pinnings/core stones to be checked for fixity.

Wall capping consolidation mortar to be checked and renewed if cracked and unstable.