

- All vegetation growing on the structure is to be removed and the stonework treated to prevent re-growth.

- It is recommended that a reliable stonemason also inspects the structure and his/her recommendations are taken into consideration when finalising the repair scope of works.
- The recommendations are to be approved by H.E.S., and may be subject to revision.
- These drawings are to be read in conjunction with Harley Haddow Structural Inspection Report and Architects drawings.
- Helifix ties positions are indicative only. Final positions to suit stone coursing

B	REVISED TO SUIT ARCHITECT'S COMMENTS	SD	AF	GA	08.07.16
A	NOTES ADDED	SD	AF	GA	29.06.16
REV	DESCRIPTION	BY	CHK	APP	DATE



**HARLEY
HADDOW**

Scale @ A1 1:50	Date 06.06.2016	Engineer A.F.
Drawing No. 301		Revision B